DESIGN & CONSTRUCTION NOTE STREET TREE SPECIFICATION

STREET TREE AND IRRIGATION DESIGN

702.04 REVIEWED: 15.03.2024

Contract Management

The contractor shall submit a comprehensive method of work statement including:

- Preparation of relevant OSH documentation. All contractors must complete City of Perth safety induction.
- Dust and noise control strategy
- CoP obstruction permit (see below) and parking bay reservations (if required)
- Traffic and pedestrian management plans (see below).
- Site plans showing excavation, stockpiling, laydown, access, fencing, parking, plant & equipment movements and storage.
- Written methodology of works including methods of excavation and installation, inspection & hold points, plant & equipment used, mitigation of noise and dust, nightworks (if required), obstructions and access requirements, clean up and make good
- Program of works including lead times for utility or City of Perth permits and approvals, inspection and hold points
- Protocols for working around high pressure gas infrastructure (ATCO) and high voltage power infrastructure (Western Power)

Traffic Management

• If/when required, traffic management plans shall be prepared by a suitably qualified professional, submitted to the City and approved prior to the commencement of works

Obstructions, permits and access

- The installation contractor is responsible for organising any relevant obstruction permits and traffic management plans to complete works.
- All contractors must complete a City of Perth safety induction
- Site area should be minimised to reduce impact on the public
- Vehicles are not permitted within parks and reserves without prior approval and issue of Parking in Reserve Permit by CoP

Site Hygiene & Environmental Controls

- The City of Perth has a Plant Pathogen Management Plan in place. Adhering to the protocols in the Plant Pathogen Management Plan will help to prevent the spread of plant pathogens.
- Vehicles are not permitted within parks and reserves
- All weed seeds, mud, soil and organic matter must be removed from clothing, footwear, tools, equipment and machinery before entering and exiting any site.
- Equipment shall be cleaned with a brush and sterilised
- All works must adhere to AS2436:2010 Guide to Noise and Vibration Control on Construction, Demolition and Maintenance Sites

